

OPERATION

OPERATOR PANEL OPERATION PROCEDURE

STEP 1: Confirm that circuit breaker (5CB) is switched ON and CONTROL POWER pilot light (2PL) is lit.

- If INCORRECT POWER pilot light (1PL) is lit, check PMR for phase rotation and voltage setting.

STEP 2: Turn ON FLOW switch (1SW).

STEP 3: Cooling probe selection switch (2SW)

- Turn 2SW to LVG - Cooling is based on leaving water control.
- Turn 2SW to RTN - Cooling is based on entering water control.

STEP 4: Turn ON COOLING switch (5SW)

STEP 5: Turn BYP/VFD switch (3SW) to require condenser fan operating mode.

- BYP - Condenser fan is started using bypass starter.
- VFD - Condenser fan is started using VFD.

It is the customer's responsibility to always follow the written operating instructions of the unit and maintain safe work practices.